

Company: \_\_\_\_\_

**PILE BID 2024**

**Pile Bid Cost Sheet**

**Port San Luis Harbor District**

**Piles**

Quantity	SIZE		Grade	Treatment	Polyurea	Unit Cost	Total	Use	Grading Rules
24	Dia. (in)	Length (ft.)	#1 structural or >	ACZA - 2.50	27' Total Length			Structural Piles Harford Pier	ASTM D25
	Butt = 12 to 13.5	45			13' From Butt				
	Tip = 8 to 10				5' From Tip				
3	Dia. (in)			Length (ft.)	ACZA - 2.50	27' Total Length			
	Butt = 14 to 16	45		13' From Butt					
	Tip = 10 to 12			5' From Tip					
6	Dia. (in)			Length (ft.)	ACZA - 2.50	33' Total Length			
	Butt = 12 to 13.5	45		7' From Butt					
	Tip = 8 to 10			5' From Tip					
6	Dia. (in)			Length (ft.)	ACZA - 2.50	38' Total Length			
	Butt = 13 to 14.5	55		7' From Butt					
	Min. Tip = 7.5			10' From Tip					
6	Dia. (in)			Length (ft.)	ACZA - 2.50	43' Total Length			
	Butt = 13 to 14.5	65		7' From Butt					
	Tip = 7			15' From Tip					
<b>Subtotal</b>						\$			
<b>Lumber Tax @ 1%</b>						\$			
<b>Sales Tax @ 7.25%</b>						\$			
<b>Delivery</b>						\$			
<b>GRAND TOTAL</b>						\$			